

# Dimond Boulevard Pavement Preservation

Planned Construction Summer 2026

## Project Has Two Typical Sections Based on Rut Depth

- High rut depths (Standard Mill/Fill) – Average 0.5” but routinely 1”
  - 1.2 miles
- Low rut depths (Thin Inlay) – Average 0.4”
  - 1.5 miles

### Standard Mill/Fill

- 2” Mill/fill
- Type V (Superpave) with Hard Aggregate & PG 64-40 binder
  - Coarse Aggregate has Nordic Abrasion less than 8

### Thin Inlay – Pooled Fund Area

- 1” Mill/fill
- Type IV Mix with Hard Aggregate & PG 64-40 Binder
  - 3/8” Minus Mix
  - Coarse aggregate has Nordic Abrasion less than 8

Pooled Fund Area:

4 – 6 lanes

AADT 18,000 – 25,000

1.5 miles in length

Overall project area is in good condition – only distresses are some longitudinal cracking and moderate rutting

